

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. <u>X</u> , R. <u>34</u> W.	G-8
2. PROPERTY CONTROLLING IN SECTION	<u>22</u> , T. <u>44</u> N. <u>X</u> , R. <u>34</u> W.	3
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____, R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 26, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law: **Note: This is a correction of a previously filed record, which is now void.**

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G8 (1/4 corner between Sections 21 & 22, T44N, R34W):**
    - Wood post (Not found. No subsequent monuments found.)
    - Sugar 16 N35W 41 (Not found. No subsequent accessories found.)
    - Sugar 14 S40E 31 (Not found. No subsequent accessories found.)
  - Corner 3 (North 1/16 corner between Sections 21 & 22, T44N, R34W):**
    - Not established in original survey nor subsequently, apparently. Found a 3" x 3" x 5' squared cedar post N52°E 76.3 ft., evidently set by measuring S from an L.E.S. post mistakenly assumed to be the section corner.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G8:** Restored on line between Sec. Corners 39.933 ch. S and 39.665 ch. N. Uneven distances were used because of belief of original survey errors in this section line. As the indications are more preponderant towards the error being in the N 1/2 mile, most of the shortage was placed there.
  - Corner 3:** Established on line between 1/4 cor. 19.967 ch. S and Sec. Cor. 19.698 ch. N. The undersigned believing that the major part of the error in the original survey measurement of this section line occurred in the N 1/2 of this half-mile segment, the S 1/2 was made proportional to the S 1/2 mile of the whole sec. line, and the difference thrown into the N 1/2 of this half-mile segment.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner G8:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap
    - Sugar Maple 6 N64°W (mag.) 13.4 ft. "1/4S, NBT"
    - Sugar Maple 5 S18°W (mag.) 23.1 ft. "1/4S, NBT"
 Declination 0°30' East.
  - Corner 3:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
    - Sugar Maple 8 S25°E (mag.) 17.0 ft. "1/16S, BT"
    - Sugar Maple 8 N62°W (mag.) 21.4 ft. "1/16S, BT"
 Declination is 1°30' East.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1978

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

