

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON COUNTY

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> <sup>N.</sup> <del>S.</del> , R. <u>34</u> <sup>EX</sup> <del>W.</del>	K8
2. PROPERTY CONTROLLING IN SECTION <u>24</u>	, T. <u>44</u> <sup>N.</sup> <del>S.</del> , R. <u>34</u> <sup>EX</sup> <del>W.</del>	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> <del>S.</del> , R. _____ <sup>E.</sup> <del>W.</del>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 8, 1977, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner K8 (1/4 corner between Sections 23 & 24, T44N, R34W):**  
 Wood post (Not found. See B for subsequent monument.)  
 Y. Birch 8 S30E 42 (" " No subsequent accessories found.)  
 Sugar 6 N36W 12 (" " " " " " " " )

**Corner 3 North 1/16 corner between Sections 23 & 24, T44N, R34W):**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner K8:** Re-established on line between Sec. Corners 39.972 ch. to N and to S. Found a 2" iron pipe N72°21'E 92.95 ft. from corner set herein, set by unknown parties, probably by guesswork, as it is so far removed from the line between Sec. Corners to N and S of it.

**Corner 3:** Re-established on line between Sec. Cor. 19.986 ch, N and 1/4 cor. 19.986 ch. S. Corner falls about 6 ft. N of a 10 ft. high rock ledge, not mentioned in the original field notes, and is 5.106 ch. S of South M.C. bet. Sec. 23 & 24.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner K8:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 14 S25°W (mag.) 14.0 ft. "1/4S, NBT"  
 W. Birch 14 N22°E (mag.) 34.7 ft. "1/4S, NBT"  
 Declination is 1°15' East

**Corner 3:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in mound of rocks.  
 Cedar 12 N29°W (mag.) 28.6 ft. "1/16S, BT"  
 Cedar 9 N89°E (mag.) 12.7 ft. "1/16S, BT"  
 Declination is 1°20' East

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE October 22, 1977  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

