

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} S. R. <u>34</u> ^{W.} E.	C-8 & C-10
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 29, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C8 (1/4 corner between Sections 19 & 20, T44N, R34W):

Wood post	(Not found. See B for subsequent monument.)
Fir 6 N75W 18	(" " No subsequent accessories found.)
Fir 7 S45E 36	(" " " " " ")

Corner C10 (1/4 corner between Sections 29 & 30, T44N, R34W):

Wood post	(Not found. See B for subsequent monument.)
Y. Birch 30 S26W 42	(" " No subsequent accessories found.)
Sugar 18 N53E 24	(" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C8: Restored on line between Sec. Cor. N0°10.2'E 40.065 ch. and Sec. Cor. S0°10.2'W 40.065 ch. Found an L.E.S. post and an iron pin set next to it (pin set by Patrick Roach, an adjoining land owner, according to his statement to the undersigned) N32°14.4'E 34.4 ft. from corner reported herein, but I do not believe it was set from any original evidence.

Corner C10: Restored on line between Sec. Cor. N0°31.2'E 40.0665 ch. and Sec. Cor. S0°31.2'W 40.0665 ch. Found an iron bolt buried vertically in approx. CL of county road N5°35.6'W 88.4 ft., set by unknown persons, apparently to represent the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C8: 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap.
 Red Maple 7 S65°E (mag.) 27.3 ft. "1/4S, NBT"
 Red Maple 5 N86°E (mag.) 24.2 ft. "1/4S, NBT"
 Declination 3°05' West

Corner C10: 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 5 S41°E (mag.) 24.1 ft. "1/4S, NBT"
 Red Maple 13 N64°W (mag.) 46.9 ft. "1/4S, NBT"
 Declination is 0°15' East

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE April 5, 1978

CHIEF OF SURVEY PARTY
Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

