

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRAN COUNTY

FOR CORNERS OF-:	LOCATED IN-:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>13</u> , T. <u>44</u> N. <del>XX</del> R. <u>34</u> E. W.		10c & 10d
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____ , RECORDED PLAT _____		_____
5. PRIVATE CLAIMS _____		_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner 10c (2nd M.C. North of Sec. Cor. 13, 14, 23, & 24, T44N, R34W, bet. 13 & 14):**  
 Wood post (Not found. No subsequent monuments found.)  
 Fir 6 N30E 50 (" " " " accessories " )
- Corner 10d (1st M.C. North of Sec. Cor. 13, 14, 23, & 24, T44N, R34W, bet. 13 & 14):**  
 Wood post (Not found. No subsequent monuments found.)  
 W. Birch 8 S75W 14 (" " " " accessories " )  
 Fir 6 S50E 20 (" " " " " " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner 10c:** Re-established 8/15/77 on true sec. line on North bank of Paint River where river's course is SE'ly. Corner is 4.169 ch. N of Sec. Cor. 13, 14, 23, & 24 and 36.015 ch. S of 1/4 cor. bet. 13 & 14. This is not the 1851 position of the river bank at this location, the bank having obviously extended southward about 100 ft. or so due to accretions of river sediment.
- Corner 10d:** Re-established 7/14/77 on true sec. line on South bank of Paint River where river's course is SE'ly. Corner is 1.600 ch. N of Sec. Cor. 13, 14, 23, & 24 and 38.584 ch. S of 1/4 cor. bet. 13 & 14.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Corner 10c:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Silver Maple 17 N10°E (mag.) 49.2 ft. "MC, NBT"  
 No others near  
 Declination 1°15' East
- Corner 10d:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 B. Ash 4 S30°W (mag.) 27.6 ft. "MC, NBT"  
 No others near  
 Declination is 1°15' East

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE October 25, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

