

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLLING IN SECTION <u>13</u> , T. <u>44</u> N. S., R. <u>34</u> E. W.		10a & 10b
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner 10a (4th M.C. North of Sec. Cor. 13, 14, 23, & 24, T44N, R34W, bet. 13 & 14):**  
 Wood post (Not found. No subsequent monuments found.)  
 Spruce 8 N15W 25 ( " " " " accessories " )  
 Spruce 10 N30E 23 ( " " " " " " )

**Corner 10b (3rd M.C. North of Sec. Cor. 13, 14, 23, & 24, T44N, R34W, bet. 13 & 14):**  
 Wood post (Not found. No subsequent monuments found.)  
 Maple 8 East 6 ( " " " " accessories " )  
 Cedar 14 S3W 20 ( " " " " " " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner 10a:** Re-established 7/13/77 on true sec. line on North bank of Paint River where river's course is SW'ly, at the foot of Upper Hemlock Rapids. Corner is 26.247 ch. S of 1/4 cor. bet. 13 & 14 and 13.937 ch. N of Sec. Cor. 13, 14, 23 & 24.

**Corner 10b:** Re-established 8/15/77 on true sec. line on South bank of Paint River where river's course is SW'ly, at the foot of Upper Hemlock Rapids. Corner is 11.877 ch. North of Sec. Cor. 13, 14, 23, & 24 and 28.307 ch. S of 1/4 cor. bet. 13 & 14.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner 10a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in mound of rocks.  
 W. Spruce 13 N34°W (mag.) 19.2 ft. "MC, NBT"  
 B. Ash 8 N14°E (mag.) 34.4 ft. "MC, NBT"  
 Declination is 1°05' East

**Corner 10b:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in mound of rocks.  
 Red Maple 8 S12°W (mag.) 38.0 ft. "MC, NBT"  
 B. Ash 8 N67°E (mag.) 8.4 ft. "MC, NBT"  
 Declination is 2°35' East

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE October 25, 1977

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

