

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T 44 N. 34 W.	G4
2. PROPERTY CONTROLLING IN SECTION 10	T 44 N. 34 W.	10a & 10b
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner G4 (1/4 corner between Sections 9 & 10, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Sugar 16 S34E 30 ( " " " " accessories " )  
 Sugar 14 N42W 14 ( " " " " " " )
- Corner 10a (South M. C. between Sections 9 & 10, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Fir 9 S51E 14 ( " " " " accessories " )  
 Fir 6 S38 1/2 W 50 ( " " " " " " )
- Corner 10b (North M. C. between Sections 9 & 10, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Cedar 16 N60W 13 ( " " " " accessories " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Fir 4 N13E 18 ( " " " " " " )
- Corner G4:** Re-established 6/2/77 proportionately on line between South M.C. 32.676 ch. S and Sec. Cor. 40.112 ch. N.
- Corner 10a:** Re-established 5/27/76 on S bank of Paint River by retracement of original meander line from East M. C. bet. Sec. 9 & 16.
- Corner 10b:** Re-established 6/2/77 on N bank of Paint River on true sec. line bet. South M.C. 2.721 ch. S and 1/4 cor. 29.955 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Monuments for all three corners:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
1. Witnesses for Corner G4: Sugar Maple 8 S 8°W (mag.) 38.0 ft. "1/4S, NBT"  
 Sugar Maple 9 N58°W (mag.) 45.1 ft. "1/4S, NBT"  
 (Declination 0°40'West)
2. Witnesses for Corner 10a.: Silver Maple 10 S39°W (mag.) 12.8 ft. "MC, NBT"  
 Silver Maple 12 N84°E (mag.) 15.6 ft. "MC, NBT"
3. Witnesses for Corner 10b: Cedar 18 N59°W (mag.) 31.8 ft. "MC, NBT"  
 Cedar 9 N35°E (mag.) 33.4 ft. "MC, NBT"  
 (Declination 0°55'West)

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1977  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

