

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T 44 <sup>N.</sup> <del>XX</del> R. 34 <sup>XX</sup> <del>W.</del>	I8
2. PROPERTY CONTROLLING IN SECTION	22, T. 44 <sup>N.</sup> <del>XX</del> R. 34 <sup>XX</sup> <del>W.</del>	7
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ <sup>N.</sup> S., R. _____ <sup>E.</sup> <del>W.</del>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 11, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner I8 (1/4 corner between Sections 22 & 23, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Tamarack 8 N15E 30 (" " " " accessories ".)  
 Spruce 8 S40W 30 (" " " " " ".)  
**Corner 7 (North 1/16 corner between Sections 22 & 23, T44N, R34W):**  
 Not established in original survey and by approximation only, subsequently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner I8:** Re-established on line between Sec. Corners 39.998 ch. to N and to S.  
**Corner 7:** Established on line between Sec. Cor. 19.999 ch. N and 1/4 cor. 19.999 ch. S. Found a 3"x3"x4' squared cedar post N60°E 55.5 ft. for a forester's approx. corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner I8:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Tamarack 10 N38°E (mag.) 11.5 ft. "1/4S, NBT"  
 Tamarack 11 S46°E (mag.) 27.2 ft. "1/4S, NBT"  
 Declination 0°00'  
**Corner 7:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap  
 Sugar Maple 12 S34°W (mag.) 1.3 ft. "1/16S, BT"  
 Sugar Maple 9 N56°E (mag.) 20.1 ft. "1/16S, BT"  
 Declination 0°45' East

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE July 28, 1977

CHIEF OF SURVEY PARTY  
*Arthur O. Enger*  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Arthur O. Enger

Michigan Department of Natural Resources  
 13581



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_