

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>XX</u> R. <u>34</u> <u>XX</u> W.	<u>M7 &amp; M8</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 24, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner M7 (Section Corner 13, 18, 19, & 24, T44N, R33-34W):**  
 Y. Birch 14 Corner Tree (Not found. See B for subsequent monument.)  
 Cedar 10 S22E 26 (Not found. No subsequent accessories found.)

**Corner M8 (1/4 corner between Sections 19 & 24, T44N, R33-34W):**  
 Ironwood post (Not found. No subsequent monuments found.)  
 Y. Birch 14 S22E 8 (" " " " accessories " )  
 Sugar 16 N40W 30 (" " " " " " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner M7:** Re-established proportionately on line between Sec. Cor. 160.203 ch. S and 1/4 cor. 40.051 ch. N. Found a 2" squared elm cut off to resemble a post S76°W 41.3 ft. from monument reported herein. Monument falls on E edge of a N & S woods road.

**Corner M8:** Re-established proportionately on line between Sec. Cor. 40.051 ch. S and Sec. Cor. 40.051 ch. N. Found a Northern Paper Mills location tag on a 12" ironwood N11½°W 11.3 ft.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner M7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Red Maple 6 (NE'ly one of a clump) S62°W (mag.) 44.1 ft. "S24, NBT"  
 Red Maple 7 N72°E (mag.) 29.3 ft. "S18, NBT"

**Corner M8:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Red Maple 6 N43°W (mag.) 23.2 ft. "1/4S, NBT"  
 Red Maple 8 S 7°E (mag.) 6.7 ft. "1/4S, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 2, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

13581

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

