

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S. R. <u>34</u> E. XX W.	I 7
2. PROPERTY CONTROLLING IN SECTION <u>15</u>	, T. <u>44</u> N. S. R. <u>34</u> E. XX W.	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 26, 19 76, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I 7 (Section Corner 14, 15, 22, & 23, T44N, R34W):

Wood post	(Not found. See B for subsequent monuments.)
Y. Birch 12 N50E 52	(" " No subsequent accessories found.)
Hemlock 16 S55W 70	(" " " " " ")

Corner 14 (South 1/16 corner between Section 14 & 15, T44N, R34W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I 7: Re-established on S'yly extension of a true line between Sec. Cor. 2, 3, 34, & 35, T44-45N, R34W and an original M.C. bet. Sec. 10 & 11 on S bank of Paint River, at the record distance S of the M. C. This seems best to resolve the distribution of measurement error found on the line between Sec. Cor. 16, 17, 20, & 21 and Sec. Cor. 13, 14, 23, & 24; that is, a variation from the original record measurement. Found an L.E.S. control post S32°08'E 49.5 ft. and another cedar post N44°32'E 41.0 ft. for approx. corners, there being no evidence to cause me to think they represented the original corner.

Corner 14: Established on line between Sec. Cor. 20.052 ch. S and 1/4 cor. 20.052 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I 7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 14 N40°E(mag.) 13.4 ft. "S14, NBT"
 Cedar 14 S9°W (mag.) 61.1 ft. "S22, NBT"

Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Cedar 9 S37°E (mag.) 31.5 ft. "1/16S, BT"
 Cedar 7 N47°W (mag.) 19.8 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 9, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

