

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> <sup>N.</sup> <del>XX</del> <sup>S.</sup> R. <u>34</u> <del>XX</del> <sup>W.</sup>	J3
2. PROPERTY CONTROLLING IN SECTION <u>10</u>	, T. <u>44</u> <sup>N.</sup> <del>XX</del> <sup>S.</sup> R. <u>34</u> <del>XX</del> <sup>W.</sup>	14a
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> <del>XX</del> <sup>S.</sup> R. _____ <del>XX</del> <sup>W.</sup>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner J3 (1/4 corner between Sections 2 & 11, T44N, R34W):
- |                     |   |
|---------------------|---|
| Wood post           | (Not found. No subsequent monuments found.) |
| Y. Birch 10 N35E 74 | ( " " " " accessories " )                   |
| Fir 8 S20W 75       | ( " " " " " " )                             |
- Corner 14a (South M.C. between Section 10 & 11, T44N, R34W):
- |                    |   |
|--------------------|---|
| Wood post          | (Not found. No subsequent monuments found.)   |
| W. Pine 10 N75E 30 | (Found. No subsequent accessories found.)     |
| Fir 9 S35W 13      | (Not found. No subsequent accessories found.) |
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner J3: Re-established 6/6/77 on line between Sec. Cor. 39.725 ch. to E and to W. Corner falls about 40 ft. S of S edge of E & W county road.
- Corner 14a: Re-monumented 5/21/76 from remains of original BT, identified by scribe marks on a slab of the witness face.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner J3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
- |                          |                      |
|--------------------------|----------------------|
| Red Maple 7 S86°W (mag.) | 27.1 ft. "1/4S, NBT" |
| Balsam 7 N44°E (mag.)    | 26.2 ft. "1/4S, NBT" |
- Declination 1°05' West
- Corner 14a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- |                              |                     |
|------------------------------|---------------------|
| Silver Maple 12 S68°E (mag.) | 35.3 ft. "MC, NBT"  |
| Cedar 16 S55°W (mag.)        | 116.8 ft. "MC, NBT" |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_


(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1977  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources  
 13581



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_