

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> ^{N.} S. , R. <u>34</u> ^{E.} W.	<u>16</u>
2. PROPERTY CONTROLLING IN SECTION <u>15</u>	T. <u>44</u> ^{N.} S. , R. <u>34</u> ^{E.} W.	<u>7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. , R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 16 (1/4 corner between Sections 14 & 15, T44N, R34W):
 Wood post (Not found. See B for subsequent monument.)
 Y. Birch 9 S30E 16 (" " . No subsequent accessories found.)
 Sugar 10 N30W 14 (" " " " " " .)

Corner 7 (North 1/16 corner between Sections 14 & 15, T44N, R34W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 16: Re-established 10/27/76 on line between Sec. Cor. 40.105 ch. to N and to S. Found a 4"x4"x4' squared cedar post N36°20'E 29.0 ft. for an approx. corner.

Corner 7: Established 10/25/76 on line between Sec. Cor. 20.052 ch. N and 1/4 cor. 20.052 ch. S. Found a 17" W. Birch blazed on 4 sides for an approx. cor. N68°W 28.0 ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 9 N25°W (mag.) 4.1 ft. "1/2S, NBT"
 Sugar Maple 5 N74°E (mag.) 1.6 ft. "1/2S, NBT"

Corner 7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 12 N38°W (mag.) 18.7 ft. "1/16S, BT"
 Red Maple 8 S54°E (mag.) 21.0 ft. "1/16S, BT"

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977

CHIEF OF SURVEY PARTY
Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

