

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>3</u> R. <u>34</u> E. <u>W.</u>	<u>G3 &amp; G2</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner G3 (Section Corner 3, 4, 9, & 10, T44N, R34W):

Wood post	(Not found. See B for subsequent monument.)
Y. Birch 16 S55E 38	(Not found. No subsequent accessories found.)
Sugar 8 N50W 93	( " " " " " " )

Corner G2 (¼ corner between Sections 3 & 4, T44N, R34W):

Wood post	(Not found. See B for Subsequent monument.)
Y. Birch 14 N16W 17	( " " . No subsequent accessories found.)
Sugar 6 S34E 47	( " " " " " " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner G3: Re-established 11/9/76 by double proportionate measurements from corners 79.578 ch. N, 72.788 ch. S, 80.910 ch. E, and 79.090 ch. W. Found an approximate corner maple post N76°23'W 35.2 ft., with Northern Paper Mills location tag saying "ABOUT COR."

Corner G2: Re-established 6/2/77 proportionately on line between Sec. Cor. 40.110 ch. S and Sec. Cor. 39.469 ch. N. Found an approximate corner spruce post lying on ground N89°W 57.0 ft. from corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner**

Corner G3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Red Maple 9 S43°W (mag.) 40.2 ft. "S9, NBT"  
 Red Maple 6 S61°E (mag.) 43.2 ft. "S10, NBT"

Corner G2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Red Maple 7 N9°E (mag.) 51.1 ft. "¼S, NBT"  
 Red Maple 8 S79°W (mag.) 61.5 ft. "¼S, NBT"  
 Declination 0°25' West

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

