

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 <sup>N.</sup> <del>XX</del> S. R. 34 <sup>XX</sup> W.	M6
2. PROPERTY CONTROLLING IN SECTION	13, T. 44 <sup>N.</sup> <del>XX</del> S. R. 34 <sup>XX</sup> W.	14
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____, S. _____, R. _____, E. _____, W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- Corner M6 (1/4 corner between Sections 13 & 18, T44N, R33-34W):**
- |                  |   |
|------------------|---|
| Sugar post       | (Not found. No subsequent monuments found.) |
| Sugar 10 S52W 25 | ( " " " " accessories " )                   |
| Fir 8 N37E 33    | ( " " " " " " )                             |
- Corner 14 (South 1/16 corner between Sections 13 & 18, T44N, R33-34W):**
- Not established in original survey nor subsequently, apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- Corner M6:** Re-established 5/20/76 at an old fence corner N and E, which is in close agreement with corners on the range line 2 miles S and 1/2 mile N.
- Corner 14:** Established 6/9/77 on line between Sec. Cor. 20.025 ch. S and 1/4 cor. 20.025 ch. N.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**
- Corner M6:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- |           |                 |          |             |
|-----------|-----------------|----------|-------------|
| W. Spruce | 3 S27°E (mag.)  | 32.9 ft. | "1/4S, NBT" |
| Aspen     | 12 S53°W (mag.) | 55.2 ft. | "1/4S, NBT" |
- Corner 14:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- |           |                |          |             |
|-----------|----------------|----------|-------------|
| Red Maple | 9 N56°W (mag.) | 32.5 ft. | "1/16S, BT" |
| Red Maple | 7 S26°E (mag.) | 23.3 ft. | "1/16S, BT" |
- Declination 1°45' West

SIGNED BY \_\_\_\_\_ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
**Arthur O. Enger**

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

