

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>34</u> S., R. <u>34</u> W.	M4 & M5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

\_\_\_\_\_  
**Arthur O. Enger**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- Corner M4** (1/4 corner between Sections 7 & 12, T44N, R33-34W):
- Birch post (Not found. No subsequent monuments found.)
  - Sugar 12 N81W 28 (" " " " accessories " .)
  - Fir 8 S76E 11 (" " " " " " .)
- Corner M5** (Section Corner 7, 12, 13, & 18, T44N, R33-34W):
- Sugar post (Not found. No subsequent monuments found.)
  - Sugar 8 S57 1/2 W 34 (" " " " accessories " .)
  - Sugar 9 N46E 18 (" " " " " " .)
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- Corner M4:** Re-established 6/6/77 at intersection of a line from N splitting fences paralleling a N & S road and a line from E splitting fences paralleling an E & W road, the latter aligning with an old fence going W. Assumed to be the corner by common report, although it is not at mid-point or on line between Sec. Corners to N and S, said point bearing N79°22.4'E 24.98 ft. from corner set here.
- Corner M5:** Re-established 5/4/76 at an old squared cedar post which is on the approx. W'ly extension of the centerline of an E & W county road to E. Position is consistent with other corners on the range line to the N & S
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: of it.**
- Corner M4:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 W. Pine 3 S29°E (mag.) 36.2 ft. "NBT"  
 Elm 5 N69°W (mag.) 16.3 ft. "1/4S, NBT"  
 Declination 3°10' East
- Corner M5:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 ⊕ chiselled in 8"x15" rock N79°W (mag.) 33.13 ft.  
 ⊕ chiselled in 3'x4' rock S69°E (mag.) 27.60 ft.

SIGNED BY \_\_\_\_\_ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977  
 CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

