

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>44</u> N. _____ R. <u>34</u> W.		<u>J5 & K5</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner J5 (1/4 corner between Sections 11 & 14, T44N, R34W):
 - Wood post (Not found. No subsequent monuments found.)
 - Sugar 18 N25E 25 (" " " " accessories ".)
 - Sugar 10 S25W 9 (" " " " " " ".)
 - Corner K5 (Section Corner 11, 12, 13, & 14, T44N, R34W):
 - Wood post (Not found. No subsequent monuments found.)
 - Spruce 10 N45W 31 (" " " " accessories ".)
 - W. Pine 30 S70E 20 (Probably found.)

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner J5: Re-established 10/25/76 on line between Sec. Cor. 39.694 ch. to E and to W. Northern Paper Mills location tag N75°E 46.0 ft. says "ABOUT 1/4 COR."
 - Corner K5: Re-monumented 5/21/76 from rotted remains of a down W. Pine from which a point set at record bearing and distance agrees with record measurements to original corners 2 miles N and 1 mile S and with river bank 3.53 ch. E. The pine is of the proper species and size and was the only one of many large pines in the area not cut down, which leads me to conjecture that it was left uncut because it was a BT.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner J5: 1" I.D. x 39" iron pipe with 3 3/4" aluminum cap
 - W. Pine Stump 30 N75°E (mag.) 46.0 ft. "1/4S, NBT"
 - Elm 10 S45°W (mag.) 54.1 ft. "1/4S, NBT"
 - Corner K5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 - W. Pine 18 N58°E (mag.) 98.6 ft. "S12, NBT"
 - W. Spruce 18 S14°W (mag.) 61.6 ft. "S14, NBT"

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

