

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. R. <u>34</u> E. W.	<u>M2 &amp; M3</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 6, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner M2 (1/2 corner between Sections 1 & 6, T44N, R33-34W):**
- Hemlock post (Not found. No subsequent monuments found.)
  - Y. Birch 12 S79E 18 ( " " " " accessories " .)
  - Y. Birch 12 N70W 12 ( " " " " " " .)
- Corner M3 (Section Corner 1, 6, 7, & 12, T44N, R33-34W):**
- Cedar post (Not found. No subsequent monuments found.)
  - Sugar 14 S72W 43 ( " " " " accessories " .)
  - Cedar 11 N53E 16 ( " " " " " " .)
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner M2:** Re-established proportionately on line between Sec. Cor. 40.062 ch. S and Sec. Cor. 39.280 ch. N.
- Corner M3:** Re-established basically by splitting the distances between fences paralleling E & W and N & S county roads and finding the intersections of the center lines thereof. Position then checked by measuring to corners to N, S, and W, which distances are 79.342 ch. (R=79.22 ch.), 79.963 ch. (R=80.00 ch.), and 80.607 ch. (R=80.71 ch.), respectively, which appears to be reasonable confirmation of the location.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner M2:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- B. Ash 8 N24°W (mag.) 2.0 ft. "1/4S, NBT"
  - B. Ash 6 S29°E (mag.) 9.4 ft. "1/4S, NBT"
- Declination 2°30' West
- Corner M3:** 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap, buried in road.
- Power Pole #N64-1314 N52°W (mag.) 49.81 ft. to nail with 3/4" brass washer stamped "WITNESS MARK".
  - ⊕ Chiselled in a rock S57°W (mag.) 35.93 ft.

SIGNED BY \_\_\_\_\_ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 15, 1977

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
**Arthur O. Enger**

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

