

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S. R. <u>34</u> E. W.	E9
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 20, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E9 (Section Corner 20, 21, 28, & 29, T44N, R34W):

Wood post	(Not found. No subsequent monuments found.)	
Y. Birch 12 S49E 27	(" " " " accessories ")	
Y. Birch 20 N75W 29	(" " " " " ")	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E9: Re-established by proportionate measurement between corners bearing N0°02.3'E 80.309 ch. and S0°04.2'E 80.309 ch. and at record distance of 120.102 ch. from original corner to W. This seems best to satisfy the original record requirement that the corner was established on the line between the corners to the N and S of it. An intersection of county roads running E & W and South is N67°47.4'E 50.69 ft., but it appears that the latter was taken entirely out of Sec. 28 and the former out of Sec. 20.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 12 S28°E (mag.) 26.3 ft. "S28, NBT"
 Sugar Maple 14 S74°W (mag.) 11.5 ft. "S29, NBT"
 8" galvanized gutter spike in road intersection N67°47.4'E 50.69 ft.

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

