

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>X</u> , R. <u>34</u> X. <u>W</u> .	G10 & G11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. <u>W</u> .	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. <u>W</u> .	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 26, 1977, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G10 (1/4 corner between Sections 27 & 28, T44N, R34W):
 - Wood post (Not found. No subsequent monuments found.)
 - Sugar 12 S55W 12 (" " " " accessories " .)
 - Sugar 16 S80E 50 (" " " " " " .)
 - Corner G11 (Section Corner 27, 28, 33, & 34, T44N, R34W):
 - Wood post (Not found. See C for subsequent monument.)
 - Y. Birch 18 S40W 53 (Not found. No subsequent accessory found.)
 - Y. Birch 12 N45E 16 (Found. Found Hemlock 10 S32E 67 lks. by NPM.)

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G10: Re-established on line between Sec. Cor. 39.936 ch. to N and to S.
 - Corner G11: Re-witnessed monument described in C, below, as set by Northern Paper Mills personnel on 12/15/1953. Y. Birch BT to NE was found by them in 1949, with scribe marks plain. Marks still visible in 1953, but in 1977 only the rotted out shell of a remnant of the tree was recognizable.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner G10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 - Sugar Maple 8 S35°W (mag.) 15.8 ft. "1/4S, NBT"
 - Sugar Maple 4 N60°E (mag.) 22.0 ft. "1/4S, NBT"
 - Declination 1°20' West
 - Corner G11: 1" I.D. (probably x 36") iron pipe with 2" brass cap, by NPM.
 - Sugar Maple 5 S65 1/2°W (mag.) 23.7 ft. "S33, NBT"
 - Sugar Maple 5 S53°E (mag.) 2.4 ft. "S34, NBT"
 - Declination 0°10' East

SIGNED BY _____ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

