

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S. R. <u>34</u> W. ^{EX}	19	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 24, 1977, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 19 (Section Corner 22, 23, 26, & 27, T44N, R34W):

Wood post		(Not found. See B for subsequent monument.)
Tamarack 10 S70E 38	(" " " " " ")	accessory.)
Fir 9 N18W 38	(" " " " " ")	" .)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 19: Re-established proportionately N & S between corners N0°06.5' E 79.996 ch. and S0°15.8' E 79.996 ch., and at record departure distance E of an original corner 279.72 ch. W. This places the corner approximately on the line between the sec. corners N and S of it, as intended in the manner of execution of the original subdivision of the twp., and also places it in agreement with the record distance E to the Paint River (67.87 ch. actual to M.C. on W bank of river, versus 67.95 ch. record distance). There is a Northern Paper Mills monument (1" I.D. iron pipe with 2" brass (over)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 19: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Cedar 7 S28°W (mag.) 2.0 ft. "S27, NBT"
 Cedar 9 S28°E (mag.) 42.0 ft. "S26, NBT"
 NPM monument is N63°32' E (true) 89.8 ft. and is re-stumped to indicate it is a witness monument.
 Declination 1°00' West

SIGNED BY _____ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

