

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. <u>X</u> , R. <u>34</u> K. <u>W.</u>	G5
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	, T. <u>44</u> N. <u>X</u> , R. <u>34</u> K. <u>W.</u>	16a
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. <u>W.</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 27, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G5 (Section Corner 9, 10, 15, & 16, T44N, R34W):

- Wood post (Not found. No subsequent monuments found.)
- Cedar 14 S41W 30 (Not found. No subsequent accessories found.)
- Cedar 8 N50E 23 (Not found. No subsequent accessories found.)

Corner 16a (East Meander Corner between Sections 9 & 16, T44N, R34W):

- Wood post (Not found. No subsequent monuments found.)
- Fir 12 S20E 11 (Not found. No subsequent monuments found.)
- Cedar 16 N81E 23 (Probably found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G5: Re-established at record distance E of East M.C. bet. Sec. 9 & 16 and record distance S of South M.C. bet. Sec. 9 & 10. Found this position to be very nearly at the record distances from original corners 2 miles N and 2 miles E.

Corner 16a: Placed a monument described below at record bearing and distance from a down and rotted cedar without marks visible, which corresponds in size and position in relation to known corners to E and N, with a record cedar bearing tree. Meander courses in both directions from the corner agree closely with the original meander notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner G5:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- Cedar 4 N32°E (mag.) 34.4 ft. "S10, NBT"
- Cedar 4 S44°W (mag.) 16.5 ft. "S16, NBT"
- Corner 16a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- Cedar 13 N68°E (mag.) 36.4 ft. "MC, NBT"
- Cedar 15 S28°W (mag.) 30.2 ft. "MC, NBT"

SIGNED BY _____ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

