

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} / _X S., R. <u>34</u> ^X / _W .	<u>E2 & F3</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ ^{N.} / _{S.} , R. _____ ^{E.} / _{W.}	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} / _{S.} , R. _____ ^{E.} / _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E2 (1/4 corner between Sections 4 & 5, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Hemlock 16 S36W 35 (" " " " accessories " .)
 Hemlock 22 N83E 9 (" " " " " " .)

Corner F3 (1/4 corner between Sections 4 & 9, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Sugar 10 S45W 45 (" " " " accessories " .)
 Fir 9 N75E 24 (" " " " " " .)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E2: Re-established 11/18/76 proportionately on line between Sec. Cor. 40.070 ch. S and Sec. Cor. 39.470 ch. N.
Corner F3: Re-established 11/10/76 on line between Sec. Cor. 39.545 ch. to E and to W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 6 S38°W (mag.) 42.9 ft. "1/4S, NBT"
 Red Maple 7 N50°E (mag.) 39.9 ft. "1/4S, NBT"

Corner F3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Balsam 6 N74°E (mag.) 13.3 ft. "1/4S, NBT"
 Balsam 5 S11°W (mag.) 16.6 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE July 28, 1977

APPROVED AND SIGNED BY Arthur O. Enger DATE _____

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

