

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>X</u> , R. <u>34</u> W.	<u>E5</u>
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	T. <u>44</u> N. <u>X</u> , R. <u>34</u> W.	<u>15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E5 (Section Corner 8, 9, 16, & 17, T44N, R34W):
 Wood post (Not found. See "B" for subsequent monuments.)
 Sugar 12 N36W 22 (Not found. No subsequent accessories found.)
 Sugar 10 S83E 38 (Not found. No subsequent accessories found.)

Corner 15 (West 1/16 corner between Sections 9 & 16, T44N, R34W):
 Not established in original survey and by approximation only, subsequently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E5: On 11/8/76 placed new monument described below at site of two squared cedar posts found in calculated corner vicinity. Nothing to indicate this is original corner location, but has more points of general agreement with the original field notes as to calls to natural features than any other place I could determine (except for call to a stream to North, however). As I could not determine any other location to be better, I accepted the posts as the corner in fact.

Corner 15: Established 11/9/76 on line between Sec. Cor. 19.829 ch. W and 1/4 cor. 19.829 ch. E. Found a 3"x3"x3 1/2' squared cedar post N39°E 36.3ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

for an approximate corner.

Corner E5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 5 S11°E (mag.) 18.4 ft. "S16, NBT"
 Red Maple 6 N52°W (mag.) 8.3 ft. "S8, NBT"

Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 4 S9°W (mag.) 10.5 ft. "1/16S, BT"
 Sugar Maple 5 N68°W (mag.) 12.8 ft. "1/16S, BT"
 Red Maple 5 N75°E (mag.) 2.9 ft. "1/16S, BT"

SIGNED BY _____ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Arhtur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

