

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} S. , R. <u>34</u> ^{XX} W.	F5
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	T. <u>44</u> ^{N.} S. , R. <u>34</u> ^{XX} W.	16b
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 18, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- Corner F5 (1/4 corner between Sections 9 & 16, T44N, R34W):**
- | | |
|------------------|---|
| Wood post | (Not found. No subsequent monuments found.) |
| Sugar 16 N22E 21 | (" " " " accessories " .) |
| Sugar 10 S39W 34 | (" " " " " " .) |
- Corner 16b (West Meander Corner between Sections 9 & 16, T44N, R34W):**
- | | |
|--------------------|---|
| Wood post | (Not found. No subsequent monuments found.) |
| Elm 12 N19W 15 | (" " " " accessories " .) |
| Fir 6 S84 1/2 W 30 | (" " " " " " .) |
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- Corner F5:** Re-established proportionately on line between Sec. Cor. 39.658 ch. W and East M.C. 29.962 ch. E.
- Corner 16b:** Re-established on true sec. line on W bank of Paint River, 4.306 ch. W of East M.C. and 65.314 ch. E of Sec. Cor. 8, 9, 16, & 17. On sec. line, water's edge is 33 links E, which still makes the distance to East M.C. about 35 links longer than record. If one assumes the original sec. line not to be exactly straight, a slight bowing to the south would probably accomodate the 35 links, as the river flows almost parallel to the sec. line at this point.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Corner F5:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Cedar 10 N83°E (mag.) 35.2 ft. "1/2S, NBT"
 Cedar 9 S29°W (mag.) 36.4 ft. "1/2S, NBT"
- Corner 16b:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 14 N15°E (mag.) 23.4 ft. "MC, NBT"
 Red Maple 20 N84°W (mag.) 51.2 ft. "MC, NBT"

SIGNED BY _____ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

