

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. S. R. <u>34</u> W. ^{XX}	K6	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	T. <u>44</u> N. S. R. <u>34</u> W. ^{XX}	10	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 13, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner K6 (1/4 corner between Sections 13 & 14, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Sugar 12 N30W 19 (" " " " accessories " .)
 Sugar 10 S60E 50 (" " " " " " .)
Corner 10 (South 1/16 corner between Sections 13 & 14, T44N, R34W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner K6: Re-established on line between Sec. Corners 40.184 ch. to N and to S.
Corner 10: Established on line between Sec. Cor. 20.092 ch. S and 1/4 cor. 20.092 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner K6: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 9 S40°W (mag.) 22.8 ft. "1/4S, NBT"
 Red Maple 9 S33°E (mag.) 17.7 ft. "1/4S, NBT"
 Declination 0°50' West
Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 5 S30°W (mag.) 35.9 ft. "1/16S, BT"
 Red Maple 4 S64°E (mag.) 10.2 ft. "1/16S, BT"
 Declination 1°20' West

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES: •

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

