

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--                             | LOCATED IN--  | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY                        | T. <u>44</u> <del>N.</del> <sup>N.</sup> R. <u>34</u> <del>W.</del> <sup>W.</sup> | H7                 |
| 2. PROPERTY CONTROLLING IN SECTION <u>15</u> | T. <u>44</u> <del>N.</del> <sup>N.</sup> R. <u>34</u> <del>W.</del> <sup>W.</sup> | 16                 |
| 3. MISCELLANEOUS PROPERTY IN SECTION         | T. _____ <sup>N.</sup> <sub>S.</sub> R. _____ <sup>E.</sup> <sub>W.</sub>         |                    |
| 4. LOT NO. _____, RECORDED PLAT _____        |   |                    |
| 5. PRIVATE CLAIMS _____                      |   |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 27, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner H7 (1/4 corner between Sections 15 & 22, T44N, R34W):**
    - Wood post (Not found. L.E.S. post N56°E 70.5 ft.)
    - Cedar 14 N31W 38 (Not found. No subsequent accessories found.)
    - Y. Birch 20 S22E 47 (Not found. No subsequent accessories found.)
  - Corner 16 (East 1/16 corner between Sections 15 & 22, T44N, R34W)**  
 Not established in original survey. Found 2" x 2" x 40" squared cedar post S77°E 40.9 ft. for a forester's approximate corner.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner H7:** Re-established on line between Sec. Cor. 39.816 ch. to E and to W. The Land Economic Survey post was set only as a control post for that survey and was not intended to be a U.S. rectangular survey corner.
  - Corner 16:** Established on line between Sec. Cor. 19.908 ch. E and 1/4 cor. 19.908 ch.W.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner H7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
    - Sugar Maple 8 N26°E (mag.) 19.5 ft. "1/4S, NBT"
    - Sugar Maple 4 S40°W (mag.) 3.6 ft. "1/4S, NBT"
  - Corner 16:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
    - Hemlock 14 N49°E (mag.) 23.7 ft. "1/16S, BT"
    - Cedar 14 S31°W (mag.) 36.8 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977

CHIEF OF SURVEY PARTY  
*Arthur O. Enger*  
 MICHIGAN REGISTERED LAND SURVEYOR  
**Arthur O. Enger**

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

