

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 44 <sup>N.</sup> <del>S.</del> , R. 34 <del>E.</del> <sup>W.</sup>	E3
2. PROPERTY CONTROLLING IN SECTION _____	8, T. 44 <sup>N.</sup> <del>S.</del> , R. 34 <del>E.</del> <sup>W.</sup>	2
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, R. _____, <sup>N.</sup> <del>S.</del> , <sup>E.</sup> <del>W.</del>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner E3 (Section Corner 4, 5, 8, & 9, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Maple 16 N86E 8 (Not found. Notsubsequent accessories found.)  
 Elm 20 S48W 25 (Not found. No subsequent accessories found.)

**Corner 2 (East 1/16 corner between Sections 5 & 8, T44N, R34W):**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner E3:** Re-established 11/5/76 at a point 79.54 ch. S of Sec. Cor. 4, 5, 32, & 33, and 160.00 ch. W of Sec. Cor. 2, 3, 10, & 11 (the record distances). This appears to be most consistent with the few natural feature calls that can be checked and in terrain where the making of measurement blunders ought to be least likely. (Some appear to have been made to the S and to the W, and it was considered, therefore, that proportionate measurements would be inappropriate.)

**Corner 2:** Established 5/27/77 on line between Sec. Cor. 20.052 ch. E and 1/4 Cor. 20.051 ch. W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner E3:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 W. Spruce 12 S16°E (mag.) 17.1 ft. "S9, NBT"  
 Elm 4 N44°E (mag.) 33.6 ft. "S4, NBT"

**Corner 2:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 W. Spruce 16 S27°E (mag.) 19.8 ft. "1/16 S, BT"  
 B. Spruce 9 North (mag.) 13.7 ft. "1/16 S, BT"  
 Declination 0°12' West

SIGNED BY \_\_\_\_\_ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977  
 CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

