

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} S. , R. <u>34</u> ^{X.} W.	<u>D3</u>	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION <u>8</u>	T. <u>44</u> ^{N.} S. , R. <u>34</u> ^{X.} W.	<u>1</u>	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____	
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D3 (1/4 corner between Sections 5 & 8, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Cedar 14 S70E 12 (Not found. No subsequent accessories found.)
 Fir 9 N20W 36 (Not found. No subsequent accessories found.)

Corner 1 (West 1/16 corner between Sections 5 & 8, T44N, R34W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D3: Re-established 5/27/77 on line between Sec. Cor. 40.103 ch. to E and to W.
Corner 1: Established 11/12/76 on line between Sec. Cor. 20.052 ch. W and 1/4 cor. 20.051 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Tamarack 8 N32°E (mag.) 18.1 ft. "1/4S, NBT"
 B. Spruce 10 N23°W (mag.) 26.5 ft. "1/4S, NBT"
 Declination 0°12' West

Corner 1: 1" I.D. x 36" pipe with 3 3/4" aluminum cap
 W. Spruce 17 N18°W (mag.) 30.8 ft. "1/16S, BT"
 W. Spruce 14 S41°W (mag.) 50.7 ft. "1/16S, BT"

SIGNED BY _____ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

