

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} / _{S.} R. <u>34</u> ^{K.} / _{W.}	H5 & I5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 25, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H5 (1/4 corner between Sections 10 & 15, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Y. Birch 12 S50E 20 (Not found. No subsequent accessories found.)
 Sugar 14 N3W 9 (Not found. No subsequent accessories found.)

Corner I5 (Section Corner 10, 11, 14, & 15, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Sugar 12 N45E 30 (Not found. No subsequent accessories found.)
 Sugar 10 S65W 37 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H5: Re-established on line between Sec. Cor. 40.059 ch. to E and to W.
Corner I5: Re-established by double proportionate measurement between corners 1 mile W, 1 mile E, 1 mile S, and 30.35 ch. N (original M.C.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 3 N32°W (mag.) 13.0 ft. "1/4S, NBT"
 Y. Birch 10 S82°W (mag.) 4.3 ft. "1/4S, NBT"
 Y. Birch 10 S76°E (mag.) 17.4 ft. "1/4S, NBT"

Corner I5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 W. Spruce 13 N17°W (mag.) 13.9 ft. "S10, NBT"
 B. Spruce 4 S69°E (mag.) 8.9 ft. "S14, NBT"

SIGNED BY _____ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

