

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. <u>9</u> R. <u>34</u> <u>X</u> E. <u>W.</u>	K2 & K3	REGISTER OF DEEDS STAMP AND FILING NUMBER _____
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W.		
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- Corner K2 (1/4 corner between Sections 1 & 2, T44N, R34W):**
- Wood post (Not found. No subsequent monuments found.)
  - Cedar 12 S35W 23 (Not found. No subsequent accessories found.)
  - Fir 8 N40E 19 (Not found. No subsequent accessories found.)
- Corner K3 (Section Corner 1, 2, 11, & 12, T44N, R34W):**
- Wood post (Not found. No subsequent monuments found.)
  - Y. Birch 12 N70E 35 (Not found. No subsequent accessories found.)
  - Cedar 14 S65W 25 (Not found. No subsequent accessories found.)
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- Corner K2:** Re-established 5/27/76 proportionately on line between Sec. Cor. 40.165 ch. S and 39.432 ch. N.
- Corner K3:** Re-established by double proportionate measurement from original corners 1 mile N, 1 mile S, and 1 mile W, and a road intersection which appears to be at a corner on the range line 1 mile E. Corner falls in W'ly track of a gravelled woods road running about N&S, 64.2 ft. S of intersection of construction centerlines of this road and an E&W county road, said intersection marked with an 8" galvanized gutter spike in road. Monument set 7/15/76.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Corner K2:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- Sugar Maple 10 N42°E (mag.) 2.8 ft. "1/4S, NBT"
  - Sugar Maple 3 S56°W (mag.) 20.3 ft. "1/4S, NBT"
- Corner K3:** 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap, buried in road.
- W. Birch 12 S88°W (mag.) 19.3 ft. "S11, NBT"
  - Red Maple 4 N71°E (mag.) 45.4 ft. "S1, NBT"
  - 8" gutter spike NO°53.5' W 64.16 ft.

SIGNED BY \_\_\_\_\_ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

