

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> ^{N.} / _{K.} , R. <u>34</u> ^{K.} / _{W.}	<u>G6 & G7</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____, S., R. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____, S., R. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 28, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G6 (¼ corner between Sections 15 & 16, T44N, R34W):
 - Wood post (Not found. No subsequent monuments found.)
 - Y. Birch 30 N41W 47 (Not found. No subsequent accessories found.)
 - Lynn 8 S31E 13 (Not found. No subsequent accessories found.)
 - Corner G7 (Section Corner 15, 16, 21, & 22, T44N, R34W):
 - Wood post (Not found. See "B" for subsequent monument.)
 - Y. Birch 16 S25W 41 (Not found. No subsequent accessories found.)
 - Sugar 14 N45E 42 (Not found. No subsequent accessories found.)

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G6: Re-established on line between Sec. Cor. 39.885 ch. to N and to S.
 - Corner G7: Re-established on S'ly extension of a line between a corner on the N twp. bdy. 3 miles N and a corner 1 mile N at record distance from the N twp. bdy., this being in accordance with the original method of subdividing the township. Corner thus set is N0°19'W 159.465 ch. from an original corner to South, S89°06.5'E 80.049 ch. from corner to West, and N89°34.5'W 79.631 ch. from corner to East. Found an L.E.S. control post N59°E 111.2 ft., which has been mistaken for the section corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner G6: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 - Sugar Maple 7 N42°E (mag.) 5.1 ft. "½S, NBT"
 - Sugar Maple 9 S77°W (mag.) 11.3 ft. "½S, NBT"
 - Corner G7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 - Sugar Maple 7 S1°W (mag.) 9.3 ft. "S21, NBT"
 - Sugar Maple 8 N77°E (mag.) 16.5 ft. "S15, NBT"

SIGNED BY _____ DATE July 28, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 28, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

