

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLLING IN SECTION <u>13</u> T. <u>44</u> N. S., R. <u>34</u> E. W.		15& 15b
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 15, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner 15 (West 1/16 corner between Sections 13 & 24, T44N, R34W):  
 Not established in original survey nor subsequently, apparently.

Corner 15b (East Meander Corner between Sections 13 & 24, T44N, R34W):  
 Wood post (Not found. No subsequent monuments found.)  
 Alder 3 S3E 9 (" " " " accessories " )  
 Ash 10 N25E 14 (" " " " " " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner 15: Established on line between Sec. Cor. 20.014 ch. W and 1/4 cor. 20.014 ch. E. Corner falls on a small level space on W side of a rock ledge, about 1/2 chain E of swamp edge.

Corner 15b: Re-established on true sec. line on E bank of Paint River, 6.200 ch. E of Sec. Cor. 13, 14, 23, & 24 and 33.828 ch. W of 1/4 cor. Bet. Sec. 13 & 24.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner 15: ● chiselled in a rock ledge  
 Cedar 6 N44°E (mag.) 4.1 ft. "1/16S, BT"  
 Spruce 6 S79°E (mag.) 4.1 ft. "BT"  
 Declination 0°05' West

Corner 15b: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Clump of 3 Silver Maples 14 S83°W (mag.) 8.6 ft. "MC, NBT"  
 No others near  
 Declination 0°20' West

SIGNED BY \_\_\_\_\_ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

