

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>34</u> S. R. <u>34</u> E. <u>W.</u>	<u>K7</u>
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	T. <u>44</u> N. <u>34</u> S. R. <u>34</u> E. <u>W.</u>	<u>15a</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. R. _____ E. <u>W.</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner K7 (Section Corner 13, 14, 23, & 24, T44N, R34W):
 - Wood post (Not found. See B for subsequent monument.)
 - Fir 9 N50W 55 (" " . No subsequent accessories found.)
 - W. Pine 40 S80E 14 (Probably found. No subsequent accessories found.)
 - Corner 15a (West Meander Corner between Sections 13 & 24, T44N, R34W):
 - Wood post (Not found. No subsequent monuments found.)
 - Maple 6 S9½W 68 (" " " " accessories " .)
 - Elm 6 N53W 46 (" " " " " " .)

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner K7: On 10/22/76 replaced a 1" x 30" aluminum table leg found in place at record bearing and distance from a rotted W. Pine stump, no marks, but of species and size corresponding to the original W. Pine BT. Agrees with distances to river .83 ch. E and 1.60 ch. N and with sec. corners 1 mile to N, S, and E.
 - Corner 15a: Re-established 7/14/77 on true sec. line on W bank of Paint River, .830 ch. E of Sec. Cor. 13, 14, 23, & 24 and 39.198 ch. W of ¼ cor. between Sections 13 & 24.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner K7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 - W. Spruce 12 N67°W (mag.) 23.5 ft. "S14, NBT"
 - W. Spruce 5 N60°E (mag.) 12.9 ft. "S13, NBT"
 - W. Birch 13 S6½°E (mag.) 7.9 ft. "S24, NBT"
 - Declination 1°20' West
 - Corner 15a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 - Twin Black Ash 13 S16°E (mag.) 21.0 ft. "MC, NBT"
 - No others near
 - Declination 1°20' West

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

