

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} _{S.} R. <u>34</u> ^{XX} _{W.}	<u>K9</u>
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	T. <u>44</u> ^{N.} _{S.} R. <u>34</u> ^{XX} _{W.}	<u>16a</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S., R. _____ E. _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 3, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- Corner K9 (Section Corner 23, 24, 25, & 26, T44N, R34W):**
- Wood post (Not found. No subsequent monuments found.)
 - Tamarack 7 N29W 27 (" " " " accessories ")
 - Cedar 8 S20E 27 (" " " " " ")
- Corner 16a (East Meander Corner between Sections 23 & 26, T44N, R34W):**
- Wood post (Not found. No subsequent monuments found.)
 - Fir 10 S60E 15 (" " " " accessories ")
 - Fir 10 N40E 25 (" " " " " ")
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- Corner K9:** Re-established by proportionate measurement between Sec. Corners 79.944 ch. to N and to S and at record distance of 80.25 ch. W of a monument at the SE corner of Sec. 24. Vicinity has been used for about the corner, as evidenced by blazed cedars facing the monument set here, and a location tag.
- Corner 16a:** Re-established on true sec. line on E bank of Paint River, 9.741 ch. W of Sec. Cor. 23, 24, 25, & 26 and 29.827 ch. E of 1/4 cor. bet. Sec. 23 & 26.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Corner K9:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- Cedar 8 S46°W (mag.) 11.7 ft. "S26, NBT"
 - Cedar 6 N26°E (mag.) 10.2 ft. "S24, NBT"
 - Cedar 6 S21°E (mag.) 14.2 ft. "S25, NBT"
- Declination 1°00' West
- Corner 16a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- Cedar 18 N56°E (mag.) 46.3 ft. "MC, NBT"
 - Cedar 20 S63°E (mag.) 17.2 ft. "MC, NBT"

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

