

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} S. , R. <u>34</u> ^{W.} E.	<u>E11 & E13</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, N. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, N. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner E11 (Section Corner 28, 29, 32, & 33, T44N, R34W):
 - Wood post (Not found. No subsequent monuments found.)
 - Sugar 16 S54½E 44 (" " " " accessories " .)
 - Sugar 8 N79W 29 (" " " " " " .)
 - Corner E13 (Section Corner 4, 5, 32, & 33, T43-44N, R34W):
 - Maple post (Not found. See B for subsequent monument.)
 - Y. Birch 18 N19E 42 (" " . No subsequent accessories found.)
 - Sugar 10 N8W 22 (" " " " " " .)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E11: Re-established 10/29/76 at an old fence corner on the W side of a county road, which is presumed to represent the latitude of the corner by common report, and which by coincidence or otherwise, falls exactly proportional to the original record distance to original corners 40.672 ch. and 80.829 ch. E in departure.

Corner E13: On 7/29/77 re-monumented this corner found previously monumented with an old, scribed, white painted cedar post supported by a 1½" I.D. x 6½" iron pipe. This is probably a Land Economic Survey control post set in the early 1930's, from what evidence is not known; these posts are ordinarily unreliable as corners, but as this one bears N89°49'W 319.628 ch. from SE twp. corner and S0°04.8'W 80.404 ch. from a corner to N, both reasonably comparable with the original survey measurements, it was considered acceptable as the corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner E11: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 - Sugar Maple 9 S81°W (mag.) 24.6 ft. "S32, NBT"
 - Sugar Maple 6 N55°E (mag.) 72.7 ft. "S28, NBT"
 - 8" galvanized gutter spike in road, East 25.83 ft.
 - Corner E13; 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 - Sugar Maple 5 N41°W (mag.) 14.2 ft. "S32, NBT"
 - Sugar Maple 4 S87°W (mag.) 5.1 ft. "S5, NBT"
 - Declination 0°15' East

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

