

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S. R. <u>34</u> W.	I11 & J11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I11 (Section Corner 26, 27, 34, & 35, T44N, R34W):

- Wood post (Not found. See B for subsequent monument.)
- Y. Birch 10 S55W 33 (" " . No subsequent accessory found.)
- Y. Birch 14 N60E 14 (Found. Sugar 14 S41E 26 lks. NBT by NPM.)

Corner J11 (¼ corner between Sections 26 & 35, T44N, R34W):

- Wood post (Not found. See B for subsequent monument.)
- Y. Birch 12 N60W 65 (" " . No subsequent accessories found.)
- Sugar 10 S5E 64 (" " . " " " " " " .)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I11: On 7/14/77 replaced a plain 1" I.D. x 36" iron pipe set by Northern Paper Mills personnel on 12/15/1953 from an original Y. Birch BT to NE. Scribe marks were readable in 1946 and 1953, but in 1977 the down and rotted remains of the BT are recognizable only as a yellow birch, not as a BT.

Corner J11: Re-established 7/12/77 at a point bearing N88°51.5'E 39.653 ch. from the Sec. Cor. to W and due West 19.872 ch. from E 1/16 cor. bet. 26 & 35, which in turn bears N86°49.7'W 19.872 ch. from Sec. Cor. to E. This must have been the route followed in the original survey in order to pass the distinct natural features including hills, stream crossings, and line trees that are recorded in the field notes. There is no way that a straight-

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

line between Sec. Corners could have been followed. ←

- Corner I11:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 9 S70°W (mag.) 9.7 ft. "S34, NBT"
 Sugar Maple 20 S37°E (mag.) 16.0 ft. "S35, BT (or NBT?)"

NOTE: This is the NPM BT, which has apparently grown 6" in diameter since 1953.

Declination 0°35' West.

- Corner J11:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 6 N51°W (mag.) 28.5 ft. "¼S, NBT"
 Sugar Maple 6 S87°W (mag.) 10.7 ft. "¼S, NBT"
 Declination 0°05' West

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: .

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

