

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. <u>X</u> , R. <u>34</u> <u>X</u> W.	K11
2. PROPERTY CONTROLLING IN SECTION <u>26</u>	, T. <u>44</u> N. <u>X</u> , R. <u>34</u> <u>X</u> W.	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner K11 (Section Corner 25, 26, 35, & 36, T44N, R34W):**

Wood post	(Not found. Found 4"x30" cedar post in place.)
Sugar 14 N25E 45	( " " . No subsequent accessories found.)
Elm 12 S30W 23	( " " " " " " .)

**Corner 16 (East 1/16 corner between Sections 26 & 35, T44N, R34W):**

Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner K11:** On 6/6/77, replaced the wood post with a new monument described below. Post probably set in late 1940's or early 1950's by Northern Paper Mills personnel. No record of what evidence was available, but probably no original evidence. Distance E and N to river checks with original record, as does distance W to original sec. corner.

**Corner 16:** Established 7/12/77 between Sec. Cor. S86°49.7'E 19.872 ch. and 1/4 corner due West 19.872 ch. There appears to have been a considerable northward deviation from a straight sec. line in order to pass the natural features called for in the original field notes, and this corner position corresponds to the record. Found a rotted hemlock stump S87°E 2.36 ch. from corner, which could have been an original line tree reported to be 2.32 ch. E. Distance W to stream is 1.27ch.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:** ← record distance is 1.18 ch.

**Corner K11:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Sugar Maple 6 N6°E (mag.) 24.6 ft. "S25, NBT"  
 Sugar Maple 8 S1°E (mag.) 39.2 ft. "S36, NBT"  
 Declination 1°45' West.

**Corner 16:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Sugar Maple 6 S66°W (mag.) 28.8 ft. "1/16S, BT"  
 Cedar 9 N32°W (mag.) 36.6 ft. "1/16S, BT"  
 Distances are horizontal. Declination 0°20' West.

SIGNED BY \_\_\_\_\_ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

