

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>34</u> E. <u>W.</u>	K10
2. PROPERTY CONTROLLING IN SECTION <u>25</u>	T. <u>44</u> N. <u>34</u> E. <u>W.</u>	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. <u>W.</u>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 3, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K10 (1/2 corner between Sections 25 & 26, T44N, R34W):
 Wood post (Not found. See B for subsequent monument.)
 Y. Birch 6 N40E (" " . No subsequent accessories found.)
 Fir 8 S43W 36 (" " " " " " " ")

Corner 3 (North 1/16 corner between Sections 25 & 26, T44N, R34W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K10: Re-established on a line running S0°51.4'E from Sec. Cor. 23, 24, 25, & 26 at the record distance of 39.99 chains, this being a line that intersects the N bank of Paint River at the record distance. Found a 1" I.D. iron pipe S85°E 50.7 ft. set by unknown persons from unknown evidence, but certainly a great deal more deflected from the straight line bet. Sec. Corners than seems warranted.

Corner 3: Established on line between Sec. Cor. N0°51.4'W 19.995 ch. and 1/2 cor. S0°51.4'E 19.995 ch.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 B. Ash 7 S21°W (mag.) 32.9 ft. "1/2S, NBT"
 Elm 6 N72°W (mag.) 19.5 ft. "1/2S, NBT"

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 W. Spruce 14 N4°W (mag.) 28.9 ft. "1/16S, BT"
 W. Spruce 9 S73°E (mag.) 18.7 ft. "1/16S, BT"

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

