

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>25</u> , T. <u>44</u>	N. S., R. <u>34</u> E. W.	10a & 10b
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. S., R. _____ E. W.	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

\_\_\_\_\_  
**Arthur O. Enger**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner 10a (North Meander Corner between Sections 25 & 26, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 W. Ash 6 S45W 30 ( " " " " accessories " )  
 Fir 8 S10E 35 ( " " " " " " )  
**Corner 10b (South Meander Corner between Sections 25 & 26, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 W. Ash 8 N3W7 ( " " " " accessories " )  
 Cedar 8 S69E 15 ( " " " " " " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner 10a:** Re-established 5/3/77 on a line running S0°51.4'E from Sec. Cor. 23, 24, 25, & 26 and intersecting the N bank of Paint River at the record distance of 43.35 chains. This appears to follow the original line according to the original field notes, although the M.C. is not on a straight line bet. Sec. Corners.  
**Corner 10b:** Re-established 6/6/77 on a line running N0°40.6'E from Sec. Cor. 25, 26, 35, & 36 and intersecting the S bank of Paint River at the record distance of 27.77 chains. The resulting distance across river to North M.C. is 8.84 ch., close to the record 8.86 ch., but is on a bearing of

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

N2°34.0'E, making a slight jog in the sec. line.  
**Corner 10a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Elm 12 S89° E (mag.) 5.0 ft. "MC, NBT"  
 Elm 8 N1°W (mag.) 13.9 ft. "MC, NBT"  
**Corner 10b:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Sugar Maple 6 S85°W (mag.) 34.2 Ft. "MC, NBT"  
 Black Ash 5 N64°W (mag.) 44.5 ft. "MC, NBT"  
 Declination 0°45' West

SIGNED BY \_\_\_\_\_ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

DATE August 1, 1977

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

