

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} S. , R. <u>34</u> ^{E.} W.	<u>M9 & M10</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 23, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M9 (Section Corner 19, 24, 25, & 30, T44N, R33-34W):

Ironwood post	(Not found. No subsequent monuments found.)
Y. Birch 14 S71E 25	(" " " " accessories ")
Fir 10 N42 ¹ / ₂ W 32	(" " " " " ")
Sugar 16 N78E 28	(" " " " " ")
Sugar 10 S30W 14	(" " " " " ")

Corner M10 (1/2 corner between Sections 25 & 30, T44N, R33-34W):

Maple post	(Not found. No subsequent monuments found.)
Cedar 12 S57E 3	(" " " " accessories ")
Cedar 10 N42 ¹ / ₂ W 26	(" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M9: Re-established proportionately on line between Sec. Cor. 80.101 ch. S and 1/2 cor. 120.152 ch. N. Found a twin 10" maple (W'ly one) which had been blazed on 4 sides for an approx. corner, perhaps in early 1950's by Northern Paper Mills personnel, whose location tag is on the E'ly one, these trees being S32°E 23.3 ft. from corner reported herein.

Corner M10; Re-established proportionately on line between Sec. Corners 40.051 ch. to N and to S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in rock mound.
Sugar Maple 12 S54°E (mag.) 2.2 ft. "S30, NBT"
Sugar Maple 8 N7°W (mag.) 30.3 ft. "S24, NBT"

Corner M10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
Red Maple 14 N26°W (mag.) 18.6 ft. "1/2S, NBT"
Cedar 10 N38°E (mag.) 52.2 ft. "1/2S, NBT"

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1977

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

