

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|---------------------------------------|---|--------------------|
| 1. PUBLIC LAND SURVEY | T 44 ^{N.} XX R. 34 ^{XX} W. | L9 |
| 2. PROPERTY CONTROLLING IN SECTION | 25, T. 44 ^{N.} XX R. 34 ^{XX} W. | 1 |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. _____ N. _____ S., R. _____ E. _____ W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 3, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner L9 (1/4 corner between Sections 24 & 25, T44N, R34W):
- | | |
|-----------------|---|
| Wood post | (Not found. No subsequent monuments found.) |
| Sugar 10 S70E 6 | (" " " " accessories ") |
| Sugar 9 N50W 21 | (" " " " " ") |
- Corner 1 (West 1/16 corner between Sections 24 & 25, T44N, R34W):
Not established in original survey nor subsequently, apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner L9: Re-established on line between Sec. Corners 40.125 ch. to E and to W.
- Corner 1: Established on line between Sec. Cor. 20.063 ch. W and 1/4 cor. 20.062 ch. E.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner L9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- | |
|--|
| Sugar Maple 10 S32°W (mag.) 84.5 ft. "1/4S, NBT" |
| Sugar Maple 12 N72°E (mag.) 71.7 ft. "1/4S, NBT" |
- Corner 1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
- | |
|--|
| Balsam 5 S52°W (mag.) 4.7 ft. "1/16S, BT" |
| B. Ash 5 N78°E (mag.) 17.8 ft. "1/16S, BT" |

SIGNED BY _____ DATE August 1, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1, 1977

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

