

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. R. <u>34</u> W.	C 4
2. PROPERTY CONTROLLING IN SECTION <u>8</u>	T. <u>44</u> N. R. <u>34</u> W.	10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C4 (1/4 corner between Sections 7 and 8, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Cedar 10 S50E 36 (" " " " accessories ")
 Fir 6 S24W 28 (" " " " " ")

Corner 10 (South 1/16 corner between Sections 7 and 8, T44N, R34W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C4: Re-established 11/3/76 on line between South M.C. 4.630 ch. N and Sec. Cor. 38.048 ch. S. There is a measurement discrepancy between record and modern measurement of this particular section line, and from calls to swamp edges in the south 1/2 mile, some of it appears to have occurred in that 1/2 mile, and some in the north 1/2 mile. The corner was placed at record distance S of the M.C. as most nearly being consistent with the original survey.

Corner 10: Established 11/2/76 on line between Sec. Cor. 19.024 ch. S and 1/4 cor. 19.024 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C4: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 B. Ash 6 S 2⁰W (mag.) 6.1 ft. "1/4S, NBT"
 B. Ash 6 N38⁰E (mag.) 26.7 ft. "1/4S, NBT"

Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in mound of rocks.
 W. Spruce 10 S55⁰E (mag.) 9.2 ft. "1/16S, BT"
 Y. Birch 8 N34⁰W (mag.) 4.2 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 27, 1977

CHIEF OF SURVEY PARTS
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

