

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S., R. <u>34</u> E. W.	A6
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 2, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A6 (1/4 corner between Sec. 13 & 18, T44N, R34-35W):  
 Hemlock 12 for corner (Not found. See B for subsequent monument)  
 Cedar 14 N50W 3 (Probably found. See B)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Replaced corner from down and burned remains of the cedar BT. This corner bears N0°03.4'E 39.788 ch. from original sec. cor. to S and S0°08.0'E 39.464 ch. from sec. cor. to N; and is 27.06 ch. N of a stream crossing, the record distance of which is 27.28 ch. It is also 2.56 ± ch. S of a swamp edge where the record distance is given as 2.50 ch. The north 3 miles of the west boundary of 44-34 was run with transit and steel tape and all objects which are of the original survey, or have color of being original, were referenced by angles and distances to them, so their actual spatial relationships could be determined and compared with the original record. The south end of the line is anchored to an (continued on back)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Cedar 10 S4°W (mag.) 29.0 ft. "1/4S, NBT"  
 Cedar 6 N6°W (mag.) 17.7 ft. "1/4S, NBT"  
 USFS Monument N59°19'W (true) 60.5 ft.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 26, 1977

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

