

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> <sup>N.</sup> <del>XX</del> R. <u>34</u> <sup>XX</sup> <del>W.</del>	A2
2. PROPERTY CONTROLLING IN SECTION <u>6</u>	T. <u>44</u> <sup>N.</sup> <del>XX</del> R. <u>34</u> <sup>XX</sup> <del>W.</del>	10a & 10b
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> S. R. _____ <sup>E.</sup> W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner A2 (1/4 corner between Sec. 1 & 6, T44N, R34-35W):**  
 Fir Post (Not found. No subsequent monuments found.)  
 Sugar 12 S59E 7 ( " " " " accessories " )  
 Sugar 12 N48W 17 ( " " " " " " )
- Corner 10a (North M.C. between Sec. 1 & 6, T44N, R34-35W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Cedar 9 N46E 36 ( " " " " accessories " )
- Corner 10b (South M.C. between Sec. 1 & 6, T44N, R34-35W):**  
 Cedar 16 meander corner. No subsequent monuments or accessories found.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner A2:** Re-established 9/29/75 on line between Sec. Cor. 39.500 ch. N and 39.931 ch. S, at record distance from the former because the distance to Paint River to South checks with record distance.
- Corner 10a:** Re-established 9/29/75 on true sec. line on north bank of Paint River, 17.540 ch. S of 1/4 cor. and 22.391 ch. N of Sec. Cor.
- Corner 10b:** Re-established 10/1/75 on true sec. line on south bank of Paint River, 20.860 ch. N of Sec. Cor. and 19.071 ch. S of 1/4 cor.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Corner A2:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 8 N23°E (mag.) 22.7 ft. "1/4S, NBT"  
 Sugar Maple 8 S21°W (mag.) 34.6 ft. "1/4S, NBT"
- Corner 10a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 W. Birch 6 N64°E (mag.) 35.1 ft. "M.C., NBT"  
 Balsam 10 N28°W (mag.) 60.4 ft. "M.C., NBT"
- Corner 10b:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap  
 Cedar 12 S27°W (mag.) 77.1 ft. "M.C., NBT"  
 Cedar 6 S 2°E (mag.) 75.2 ft. "M.C., NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE January 26, 1977

CHIEF OF SURVEY PARTY  
*Arthur O. Enger*  
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

