

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 44 N. S. , R. 34 E. W.	A5
2. PROPERTY CONTROLLING IN SECTION _____ 18	T. 44 N. S. , R. 34 E. W.	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. , R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A5 (Section Corner 13, 18, 19, & 24, T44N, R34-35W):
 Y. Birch post (Not found. No subsequent monuments found.)
 Sugar 8 N36E 37 (" " " " accessories ")
 Cedar 18 S76W 36 (Found. " " " ")

Corner 3 (North 1/16 corner between Sections 13 & 18, T44N, R34-35W):
 Not established in original survey, and by approximation only, subsequently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A5: On 4/29/76, replaced corner by reference to original cedar BT, now a burned stump with part of lower blaze visible. Original line tree is 8.326 ch. S and stream is 12.73 ch. N, very close to original record distances. Found old blaze facing corner on an 18" aspen N60°E 33.5 ft.

Corner 3: Established 11/4/76 on line between Sec. Cor. 19.732 ch. N and 1/4 corner 19.732 ch. S. Found a 4"x4"x5' squared cedar post S22°W 16.3 ft. for an approximate corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 B. Spruce 9 S51°W (mag.) 45.9 ft. "S24, NBT"
 Balsam 6 S26°E (mag.) 41.5 ft. "S19, NBT"

Corner 3: 1" I.D. x 39" iron pipe with 3 3/4" aluminum cap.
 Elm 7 N72°W (mag.) 19.2 ft. "1/16S, BT"
 Elm 7 N34°E (mag.) 24.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE January 26, 1977

CHIEF OF SURVEY PARTY
Arthur O. Enger
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

