

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>XX</u> R. <u>34</u> W. <u>XX</u>	<u>A3 &amp; A4</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 1, 19 75, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner A3 (Section Corner 1, 6, 7, & 12, T44N, R34-35W):
    - Spruce post (Not found. No subsequent monuments found.)
    - Hemlock 10 N30E 25 (" " " " accessories " )
    - Hemlock 18 S16W 30 ( Probably found. No subsequent accessories found.)
  - Corner A4 (1/4 corner between Sections 7 & 12, T44N, R34-35W):
    - Cedar post (Not found. No subsequent monuments found.)
    - Cedar 16 N32W 19 (" " " " accessories " )
    - W. Pine 16 S83E 26 (Probably found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A3: Replaced by reference to down and rotted, but recognizable, Hemlock 18 S16W 30 original BT. From appearance, tree was cut down by loggers, and the butt log left while the rest of the bole was removed. Corner is S0°12'E 79.431 ch. from original twp. cor. N (R = 79.50 ch.), and fits almost exactly with river crossing N.

Corner A4: Replaced by reference to stump of a rotted W. Pine 16 S83E 26 original BT, presumed to be such by its relationship to other corners and line trees N & S of it. Corner is N0°28.1'E 28.251 ch. from a W. Pine 14 L. T. (R = 28.29 ch.) and N0°17'E 39.948 ch. from Sec. Cor. to S. However, it is S0°16.3'W 40.237 ch. from Sec. Cor. to N. Record distance for the mile is 80.00 ch.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A3: 1" I.D. x 36" iron pipe with 3½" aluminum cap.  
 Sugar Maple 7 S45°W (mag.) 26.3 ft. "S12, NBT"  
 Sugar Maple 7 S82°E (mag.) 7.5 ft. "S 7, NBT"  
 Variation 2°00' West

Corner A4: 1" I.D. x 36" iron pipe with 3½" aluminum cap.  
 Red Maple 10 S72°W (mag.) 7.2 ft. "1/4S, NBT"  
 Sugar Maple 6 S75°E (mag.) 8.5 ft. "1/4S, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 26, 1977  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

