

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. R. <u>34</u> K. W.	C 6
2. PROPERTY CONTROLLING IN SECTION <u>18</u>	T. <u>44</u> N. R. <u>34</u> K. W.	7
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 2, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C6 (1/4 corner between Sections 17 & 18, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Cedar 10 N25E 7 (" " " " accessories ")
 Fir 8 S35W 36 (" " " " " ")

Corner 7 (North 1/16 corner between Sections 17 & 18, T44N, R34W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C6: Re-established on line between Sec. Cor. 40.130 ch. S (the record distance) and Sec. Cor. 38.311 ch. N. Found this section line to be short of the record distance by 1.819 ch., apparently due to mistakes made in the original survey. The position of this corner was selected on the basis of agreement with a swamp edge 3.13 ch. N and with a stream crossing 13.37 ch. S, in order to resolve the discrepancy.

Corner 7: Established on line between Sec. Cor. 19.156 ch. N and 1/4 cor. 19.155 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C6: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Tamarack 14 N25°W (mag.) 69.3 ft. "1/4S, NBT"
 Cherry 10 S87°W (mag.) 27.4 ft. "1/4S, NBT"
 Elm 8 N78°E (mag.) 32.0 ft. "1/4S, NBT"
Corner 7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 5 N17°W (mag.) 25.8 ft. "1/16S, BT"
 Red Maple 5 S82°E (mag.) 17.8 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 26, 1977

MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

