

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> <sup>N.</sup> <del>X36</del> , R. <u>34</u> <sup>XX</sup> <del>W.</del>	D7
2. PROPERTY CONTROLLING IN SECTION <u>17</u>	, T. <u>44</u> <sup>N.</sup> <del>X36</del> , R. <u>34</u> <sup>XX</sup> <del>W.</del>	14a
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> S., R. _____ <sup>E.</sup> W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner D7 (1/4 corner between Sections 17 & 20, T44N, R34W):
- Wood post (Not found. See B for subsequent monument.)
  - Sugar 20 N 9W 24 ( " " No subsequent accessories found.)
  - Sugar 12 S30½E 21 ( " " " " " " )
- Corner 14a (North M.C. between Sections 16 & 17, T44N, R34W):
- Wood post (Not found. No subsequent monuments found.)
  - Cedar 12 N22E 66 ( " " " " accessories " )
  - Cedar 10 N28W 59 ( " " " " " " )
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner D7: Re-established 10/29/76 on line between Sec. Cor. 39.99½ ch. to E and to W. Found an L. E. S. control post, plainly scribed "APP" (for APPROXIMATE), S23°E 30.8 ft., indicating it was not intended to necessarily represent the true corner position.
- Corner 14a: Re-established 11/8/76 on N. bank of Paint River at record distance of 60.34 ch. S of post at Sec. Cor. 8, 9, 16, & 17. This appears to be very consistent with the original meander notes of the river.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner D7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
- Sugar Maple 9 S46°W (mag.) 7.7 ft. "1/4S, NBT"
  - Sugar Maple 11 N 3°W (mag.) 21.7 ft. "1/4S, NBT"
- Corner 14a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
- W. Birch 3 N10°E (mag.) 15.0 ft. "MC, NBT"
  - Elm 8 S53°W (mag.) 17.3 ft. "MC, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE February 23, 1977  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

