

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>5</u> , T. <u>44</u> XX N. S., R. <u>34</u> XX W.		3 & 3a
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 5, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 3 (North 1/16 corner between Sections 5 & 6, T44N, R34W):
Not established in original survey nor subsequently, apparently.

Corner 3a (North M.C. between Sections 5 & 6, T44N, R34W):

Wood post	(Not found. No subsequent monuments found.)	
Cedar 12 N65E 15	(" " " " accessories ")	
Elm 6 N17W 8	(" " " " " ")	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 3: Established proportionately on line between Sec. Cor. 19.535 ch. N and 1/4 cor. 20.065 ch. S.

Corner 3a: Re-established on true section line on North Bank of Net River on line between Sec. Cor. 35.43 ch. N and 1/4 cor. 4.17 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
W. Spruce 22 N15°W (mag.) 88.2 ft. "1/16S, BT"
Red Pine 20 N81°W (mag.) 122.1 ft. "1/16S, BT"

Corner 3a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Cedar 10 (leaning) N76°E (mag.) 22.2 ft. "MC, NBT"
W. Spruce 14 S34°E (mag.) 6.3 ft. "MC, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 23, 1977

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

