

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 ^{N.} S. R. 34 ^{W.} E.	C2
2. PROPERTY CONTROLLING IN SECTION 5	T. 44 ^{N.} S. R. 34 ^{W.} E.	10
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ ^{N.} S. R. _____ ^{W.} E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 10, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C2 (1/4 corner between Sections 5 & 6, T44N, R34W):

Wood post	(Not found. No subsequent monuments found.)	
Spruce 12 S37W 20	(" " " " accessories ")	
Spruce 6 N64W 38	(" " " " " ")	

Corner 10 (South 1/16 corner between Sections 5 & 6, T44N, R34W):
Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C2: Re-established on line between Sec. Cor. 39.325 ch. S and 39.600 ch. N. This distribution of the distance best fits the original field note call to the Net River 2.14 ch. N.

Corner 10: Established on line between Sec. Cor. 19.663 ch. S and 1/4 corner 19.663 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in mound of rocks.
Elm 8 N 3°E (mag.) 17.9 ft. "1/4S, NBT"
Elm 6 S56°E (mag.) 17.0 ft. "1/4S, NBT"

Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
B. Spruce 12 N38°E (mag.) 21.6 ft. "1/16S, BT"
B. Spruce 10 S38°W (mag.) 9.5 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 23, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

