

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. <u>44</u> <sup>N.</sup> <del>36</del> , R. <u>34</u> <sup>XIX</sup> <del>W.</del>	B3	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROL- ING IN SECTION _____	T. <u>44</u> <sup>N.</sup> <del>XIX</del> , R. <u>34</u> <sup>XIX</sup> <del>W.</del>	15a	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> _____, R. _____ <sup>E.</sup> _____ <del>W.</del>		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 25, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner B3 (1/4 corner between Sections 6 & 7, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Maple 6 S35E 12 ( " " " " accessories " )  
 Spruce 10 N31W 23 ( " " " " " " )

**Corner 15a (East M.C. on Paint River between Sections 6 & 7, T44N, R34W):**  
 Wood post (Not found. No subsequent monuments found.)  
 Cedar 6 S50E 6 ( " " " " accessories " )  
 W. Pine 12 N38E 35 (Found. No subsequent accessories found.)

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner B3:** Re-established on line between original M.C.'s S89°27.5'W 26.798 ch. and N89°27.5'E 10.643 ch.  
**Corner 15a:** Placed a new monument at record bearing and distance from stump of original W. Pine BT, identified by charred lower axe blaze with notch, and possible faint traces of scribe marks. This corner bears N88°45.5'E 12.533 ch. from original Sec. Cor. to W and S89°27.5'W 37.441 ch. from original M.C. to E on W bank of Net River. The original record says they are all on a straight line bearing N89°26'E, with distances between them of 12.43 ch. and 38.07 ch., respectively.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner B3:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Aspen 11 S51°W (mag.) 11.4 ft. "1/4S, NBT"  
 W. Spruce 9 N56°W (mag.) 19.0 ft. "1/4S, NBT"  
**Corner 15a:** 1" x 36" iron pipe with 3 3/4" aluminum cap.  
 W. Spruce 8 S53°E (mag.) 39.5 ft. "MC, NBT"  
 W. Spruce 13 N14°W (mag.) 12.0 ft. "MC, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE February 23, 1977

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

